

MAKHADO MUNICIPALITY

QUOTE NO. MAK122/2016/2017

DESCRIPTION: CONSTRUCTION OF ZAMENKOMSTE PAYPOINT OFFICE

All interested service providers are hereby invited to submit written quotations for the ZAMEKOMSTE PAY POINT OFFICE

NB: COMPULSORY BRIEFING SESSION WILL BE HELD ON WEDNESDAY ,26 JULY 2017 AT 14H00 AT ZAMENKOMSTE PAY POINT OFFICE (ZAMENKOMSTER VILLAGE , KUTAMA)

SCOPE OF WORK

ITEM	SCOPE OF WORK
1	<p>FOUNDATION</p> <ul style="list-style-type: none">• 10m x 10m site clearance to make allowance for working space• Set out 6160 x 4440 foundation (outside measurement of the building)• Make allowance of 600 x 600 trenches with total length of the building outside• Use 10mm tensile steel as reinforcement in trench and 8mm round bars @ 1200mm c/c as stripes. Steel work box must have allowance of 50mm on each side of the trench wall and underneath. (Do not weld steel in foundation)• Cast 20mpa concrete strip in the trench 300 x 600• Allow the curing of concrete for 7 days• Construct a foundation wall as per the slope's natural ground level and allow 150mm from NGL to the DPC (Damp proof course)• Fill the foundation with gravel and compact. Also make allowance of 75mm concrete slab and insert mesh wire of 5mm, cast a 20mpa concrete slab and allow the slab curing period.
2	<p>SUPERSTRUCTURE</p> <ul style="list-style-type: none">• Lay 9inch damp proof course SABS approved to start with the construction of one brick wall until the underside of the wall plate.• Brick force SABS approved to be executed at four course interval• Door frames must be of the same height with the window frames and welded security frames.• Walls must be plastered internally and externally by 20mm thick plaster.• Plastered walls to be painted with cream white G377 and Trim 1m high from the ground by Windsor green G33
3	<p>ROOF</p> <ul style="list-style-type: none">• The gable roofs trusses are treated timbers consisting of 114 x 38 rafters, king post, strut, queen post and tie beam. 76 x 50 purlins.• The height of the king post must be 1000mm and the open overhang is 600mm• Use 3mm thick IBR roof sheeting and IBR ridge.• The vertical truss members must fastened M10 bolts top and bottom• All exposed timbers must be painted by cabollinium.

	<ul style="list-style-type: none"> • Cover the overhang by 220 x 20mm fascia board and barge board on the side the gable wall
4	<p>CEILING</p> <ul style="list-style-type: none"> • Construct ceiling frame 38 x 38 battens. • Use asbestos ceiling boards and with standard cornice and strip • Paint ceiling in POLVIN white paint • The ceiling for the strong room must be casted with 75mm reinforced concrete slab.
5	<p>GLASSES AND DOORS</p> <ul style="list-style-type: none"> • Use obscure 3mm thick glasses for windows and weld 10mm round bars burglar proof. • Heavy duty doors must have shooters inside and heavy duty lock • Weld a security door using 25 x 25 square tubes with a frame at the entrance door with heavy duty security lock
6	<p>FLOOR FINISH</p> <ul style="list-style-type: none"> • Floor must be finished off by 20mm smooth cement topping.
	<p>The contractor should check the following before living the site</p> <ul style="list-style-type: none"> • All completed work area must be cleaned and dust free • All rubbles must be transported to the dumping site • All appliances are tested and are in working condition

Requirements

- **Valid Tax Compliance Status Pin Issued**
- **Copy of Company Registration Certificate**
- **Certified Copy/Copies of Company Owner(s) ID Books**
- **CIDB Grade 01 GB**
- **Certified copy Sworn Affidavit BBBEE Certificate**
- **Copy of CSD Summary Report**
- **Proof of Latest Payment of Municipal Services/ Account or Lease Agreement or Letter from Traditional Authority**

Quotations must be as follows:

1. be signed by an authorized person of the supplier
2. be on an original letter head of the company/enterprise
3. be valid for a period of sixty (60) days from the closing date
4. be accompanied by an original valid SARS Tax Clearance Certificate.

5. be accompanied by fully completed MBD 6.1 and MBD 4 obtainable from the municipality or can be downloaded from municipal website www.makhado.gov.za.

Fully priced and signed quotations must be sealed in an envelope clearly marked quote number “**MAK122/2016-2017**” & description “**CONSTRUCTION OF ZAMEKOMSTE PAYPOINT OFFICE**” and be deposited in the tender box at the foyer of the Civic Centre at the physical address reflected below by no later than **12H00 of 02 AUGUST 2017**

Quotations received will be assessed in accordance with the Municipal Supply Chain Management Regulations, 2005 read with Council’s Supply Chain Management Policy and 80/20 points scoring will be used. Preference points will be allocated according to BBBEE rating.

Please Note:

1. No quotation by facsimile or by e-mail will be accepted.
2. Enquiries in this regard must be directed to **Mr RALESHUKU MG** at telephone number **082 043 5750** during office hours.
3. Council reserves the right not to accept lowest or any quotation or to accept part of a quotation only.
4. Admin enquiries can be directed to **Ms Ntsieni TP and Mr Ramabulana M** at **015 519 3129/3179/3171/3024**

Civic Centre
83 Krogh Street
LOUIS TRICHARDT
0920

Notice 176/2017
File no: 8/3/2/1
M J KANWENDO
ACTING MUNICIPAL MANAGER